



**Brian J. Wendling**  
**Public Works Commissioner**  
 Governmental Center  
 111 S. Michigan Ave., Suite 103  
 Saginaw, MI 48602  
 Phone 989-790-5258  
 Fax 989-790-5259

**SAGINAW COUNTY PUBLIC WORKS COMMISSIONER**

**EASTWOOD DRAIN**

**NOTICE OF LETTING**

**NOTICE OF LETTING**

**DATE:** May 10, 2023  
**TIME:** 10:00 a.m.  
**LOCATION:** Spicer Group, Inc.  
 230 S. Washington Avenue  
 Saginaw, MI 48607  
**QUESTIONS:** (989) 280-2109

The Saginaw County Public Works Commissioner will meet on the above date, time and location to receive construction bids for the Eastwood Drain. Bids will then be opened and publicly announced.

The Eastwood Drain will be let in 2 Divisions as follows, each section having the length, average depth and width as shown on plans and/or described below:

*Said Drain is an existing open channel drain that is approximately 2.5 miles in length and contains a stormwater pump station containing 2 pumps and appurtenances. The open channel has a width of 4' to 10' and average depth of 6'. This Notice of Letting, the plans, specifications, and bid proposal shall be considered a part of the contract. The following items will be required, and a contract let for same:*

**EASTWOOD DRAIN - PUMP STATION - DIVISION I**

**OPEN CHANNEL CONSTRUCTION**

- 198 Lin. Ft. Open Channel Excavation - 10' Drain Bottom
- 198 Lin. Ft. Spoil Leveling (Both Sides)

**SITWORK**

- 1 Lump Sum Site Clearing
- 1 Lump Sum Temporary Dewatering and Cofferdams
- 1 Lump Sum Demolition
- 1 Lump Sum Sitework and Grading
- 50 Sq. Yd. Riprap Bank Protection
- 5,400 Sq. Ft. Aggregate Base, 22A, 8"
- 1 Lump Sum Soil Erosion and Sedimentation Control
- 1 Lump Sum Cleanup and Restoration
- 1 Lump Sum Seeding, Fertilizing, and Mulching

**PUMP STATION**

- 2 Each Carry CP12 60 HP High-Volume Axial Flow Pump
- 1 Lump Sum 24" Discharge Pipes and Fittings, Complete
- 2 Each Precast Concrete Headwall w/out Baffle
- 2 Each 24" Stainless Steel Flapgate

2	Each	6' Dia. MH/CB
48	Lin. Ft.	48" RCP w/ Tie Plates
1	Lump Sum	Concrete Headwall Structure, Complete
1	Lump Sum	Fabricated Service Platform, Complete
1	Lump Sum	Fabricated Bar Screen, Complete
8	Each	Safety Bollard
50	Cu. Yd.	Sub Grade Undercutting (As-Needed)

**ELECTRICAL**

1	Lump Sum	Electrical and Controls, Complete
1	Lump Sum	Site Lighting and Cameras, Complete

**MISCELLANEOUS**

1	Lump Sum	Mobilization
15	Days	Inspection Days (Minimum)

**ALTERNATE BID ITEMS**

1	Lump Sum	20" Discharge Pipes and Fittings, Complete
2	Each	20" Stainless Steel Flapgate

**EASTWOOD DRAIN - OPEN CHANNEL - DIVISION II**

**OPEN CHANNEL CONSTRUCTION**

2,780	Lin. Ft.	Open Channel Excavation - 10' Bottom (Sta. 2+00 to Sta. 31+20)
1,810	Lin. Ft.	Open Channel Excavation - 8' Bottom (Sta. 31+20 to Sta. 50+00)
1,982	Lin. Ft.	Open Channel Excavation - 6' Bottom (Sta. 50+00 to Sta. 71+12)
1,128	Lin. Ft.	Open Channel Construction - 6' Bottom (Sta. 71+12 to Sta. 83+20)
5,126	Lin. Ft.	Open Channel Excavation - 4' Bottom (Sta. 83+20 to Sta. 134+46)
4,920	Lin. Ft.	Spoils Management (Sta. 31+20 to Sta. 83+20)
5,126	Lin. Ft.	Spoil Leveling (One Side) (Sta. 83+20 to Sta. 134+46)
2,780	Lin. Ft.	Spoil Leveling (Both Sides) (Sta. 2+00 to Sta. 31+20)
5,203	Lin. Ft.	Road Shoulder Improvements (Both Sides of Road) (Sta. 31+10 to Sta. 56+29) (Sta. 71+22 to Sta. 83+20) (Br. 3 to 1486 Ft. East of Br. 3)
2,945	Lin. Ft.	Road Shoulder Improvements (One Side of Road) (Sta. 56+29 to Sta. 71+22) (1486' East of Br. 3 to 275' East of Ambrose)
1	Lump Sum	Site Clearing

**CROSSINGS**

**No. 1 Station 3+59 - Section 32 Farms LLC - Native Drive**

1	Lump Sum	Remove Existing Crossing
---	----------	--------------------------

**No. 2 Station 14+43 - Section 32 Farms LLC - Native Drive**

40 Lin. Ft. 84" RCP (Installation Only)  
No. 3 Station 31+57 - Section 32 Farms LLC - Native Drive  
 140 Lin. Ft. 60" HP Storm (2 Barrels)  
No. 4 Station 57+65 - Section 32 Farms LLC - Gravel Drive  
 60 Lin. Ft. 60" HP Storm  
No. 5 Station 67+72 - RC Heritage Land Company LLC - Gravel Drive  
 70 Lin. Ft. 60" HP Storm  
No. 6 Station 82+65 - RC Heritage Land Company LLC - Gravel Drive  
 70 Lin. Ft. 60" HP Storm

**SCRC CROSS CULVERTS**

Station 56+25 - Curtis Road

50 Lin. Ft. 24" HP Storm  
 2 Each 24" Metal Flared End Section

**BRANCH 1**

**OPEN CHANNEL CONSTRUCTION**

1,126 Lin. Ft. Open Channel Excavation - 3' Bottom  
 1,126 Lin. Ft. Spoil Leveling (One side)  
 1 Lump Sum Site Clearing

**CROSSINGS**

No. 7 Station 0+34 - W Curtis Road - Gravel Road

80 Lin. Ft. 36" HP Storm  
 1 Each 36" Metal Flared End Section

**BRANCH 2**

**OPEN CHANNEL CONSTRUCTION**

3,415 Lin. Ft. Open Channel Excavation - 6' Bottom  
 3,415 Lin. Ft. Spoil Leveling (One side)  
 1 Lump Sum Site Clearing

**CROSSINGS**

No. 7 Station 0+46 - Section 32 Farms LLC - Gravel Drive

50 Lin. Ft. 42" HP Storm

No. 8 Station 24+41 - Section 32 Farms LLC - Gravel Drive

60 Lin. Ft. 42" HP Storm

**BRANCH 3**

**OPEN CHANNEL CONSTRUCTION**

1,136 Lin. Ft. Channel Cleanout - 4' Bottom  
 1,136 Lin. Ft. Spoil Leveling (Both sides)  
 1 Lump Sum Ditch Plug  
 1 Lump Sum Site Clearing

**CROSSINGS**

No. 9 Station 0+31 - W Curtis Road - Gravel Road

70 Lin. Ft. 48" HP Storm  
 2 Each 48" Metal Flared End Section

**SOIL EROSION AND SEDIMENT CONTROL**

450 Sq. Yds. Plain Miscellaneous Riprap  
 400 Lin. Ft. Plain Riprap Spillway  
 100 Lin. Ft. Plain Riprap Toe of Slope Protection  
 20 Each Plain Riprap Splash Pad

3	Each	15" Surface Outlet Tube - 35'
1,750	Lin. Ft.	6" Dia. Field Tile/Header Tile Relocation
100	Lin. Ft.	8" Header Tile Relocation
100	Lin. Ft.	10" Header Tile Relocation
3	Each	10" and 12" Tile Outlet Repair
5	Each	6" to 8" Tile Outlet Repair
5	Each	4" & Smaller Tile Outlet Repair
120	Lin. Ft.	24" HP Storm Maint. Lane Culvert
1	Each	Precast Concrete Headwall w/out Baffle (30" Equivalent Headwall to Accommodate Flapgate)
1	Each	24" Flap Gate (Fontaine Series 60 - Flatback)
1	Each	24" Flap Gate / Connect to HP Storm (Agri Drain - Spigotback)
1	Lump Sum	Seeding, Fertilizing, and Mulching
1	Lump Sum	Cleanup and Restoration

### MISCELLANEOUS ITEMS

1	Lump Sum	Traffic Control
---	----------	-----------------

### ALTERNATE BID ITEMS

#### No. 3 Station 31+57 - Section 32 Farms LLC - Native Drive

64	Lin. Ft.	103" Rise x 71" Span CMPA (3"x1", 12 Ga.)
----	----------	---

#### No. 4 Station 57+65 - Section 32 Farms LLC - Gravel Drive

60	Lin. Ft.	60" CMP (3"x1", 12 Ga.)
----	----------	-------------------------

#### No. 5 Station 67+72 - RC Heritage Land Company LLC - Gravel Drive

68	Lin. Ft.	60" CMP (3"x1", 12 Ga.)
----	----------	-------------------------

#### No. 6 Station 82+65 - RC Heritage Land Company LLC - Gravel Drive

68	Lin. Ft.	60" CMP (3"x1", 12 Ga.)
----	----------	-------------------------

#### No. 7 Station 0+46 - Section 32 Farms LLC - Gravel Drive

48	Lin. Ft.	42" CMP (2-2/3"x1/2", 14 Ga.)
----	----------	-------------------------------

#### No. 8 Station 24+41 - Section 32 Farms LLC - Gravel Drive

52	Lin. Ft.	42" CMP (2-2/3"x1/2", 14 Ga.)
----	----------	-------------------------------

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at the Saginaw County Public Works Commissioner's Office and available to interested parties. Bidding Documents, including plans and specifications, may be examined, beginning April 13, 2023 at the following:

Online at <http://www.saginawcounty.com/PublicWorks/Current-Projects.aspx>


Hard copies of Bidding Documents may be obtained upon payment of a \$100.00 – per Division *non-refundable* fee, beginning on April 13, 2023. An additional *non-refundable* charge of \$10.00 will be required for mailing out Bidding Documents. To order hard copies, please contact Ms. Angie McCullen at Spicer Group at (989) 921-5538.

A security deposit drawn payable to the **Eastwood Drain Drainage District** in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

A **mandatory pre-bid conference** will be held at **9:00 a.m.** on the **19<sup>th</sup> day of April, 2023**, at the office of Spicer Group, Inc., 230 S. Washington Avenue, Saginaw, Michigan 48607. It is a requirement that any prospective General Contractor bidding attend this meeting. Representatives of the Drainage District and Spicer Group, Inc. will be present to discuss the project. Attendance is required for sealed bids to be accepted. Spicer Group, Inc. will transmit to all prospective bidders of record an Addendum as Spicer Group, Inc. considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be legally effective.

The Contract will be awarded to the lowest responsive and responsible bidder for each Division giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

Dated: April 13, 2023

  
\_\_\_\_\_  
Brian J. Wendling  
Saginaw County Public Works Commissioner