



Brian J. Wendling
Public Works Commissioner
 Governmental Center
 111 S. Michigan Ave., Suite 103
 Saginaw, MI 48602
 Phone 989-790-5258
 Fax 989-790-5259

SAGINAW COUNTY PUBLIC WORKS COMMISSIONER

NEW TAMARACK DRAIN

NOTICE OF LETTING

NOTICE OF LETTING

DATE: May 2, 2024
TIME: 11:00 a.m.
LOCATION: Spicer Group, Inc.
 230 S. Washington Avenue
 Saginaw, MI 48607
QUESTIONS: (989) 280-2109

The Saginaw County Public Works Commissioner will meet on the above date, time, and location to receive construction bids for the New Tamarack Drain. Bids will then be opened and publicly announced.

The New Tamarack Drain will be let in 1 section as follows, having the length, average depth and width as set forth:

Said Drain is an open channel, approximately 4.5 miles in length, and has an average depth of 8 feet and an average bottom width of 6 feet. This Notice of Letting, the plans, specifications, and bid proposal shall be considered a part of the contract. The following items will be required, and a contract let for same:

NEW TAMARACK DRAIN

OPEN CHANNEL CONSTRUCTION

20,058	Lin. Ft.	Open Channel Excavation
397	Lin. Ft.	Pilot Channel Excavation
15,059	Lin. Ft.	Spoil Leveling
4,999	Lin. Ft.	Spoil Hauling
397	Lin. Ft.	Spoil Hauling - Limited Access
1	Lump Sum	Site Clearing
1	Lum Sum	Site Clearing - Limited Access

OPEN CHANNEL CONSTRUCTION - SWAN CREEK ROAD BRANCH

1,400	Lin. Ft.	Open Channel Excavation
1,400	Lin. Ft.	Spoil Hauling

OPEN CHANNEL CONSTRUCTION - BRANCH NO. 1

1,238	Lin. Ft.	Open Channel Excavation
1,238	Lin. Ft.	Spoil Hauling

CROSSINGS - MAIN LINE

No. 1 Station 49+20 - CMPA - Hart Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

No. 2 Station 77+68 - CMP - Buckbee, F and Schmidt, M & L - Native Driveway

1 Lump Sum Remove Existing Crossing

No. 3 Station 90+80 - Concrete Bridge - Swan Creek Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

1 Lump Sum Guardrail Modifications

No. 4 Station 103+87 - Steel Culvert - Consumers Power Company - Collapsed Wooden Bridge

1 Lump Sum Remove Existing Crossing

No. 5 Station 108+77 - CMP - Kolhagen, J & K - Gravel Driveway

58 Lin Ft. 95" x 67" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 6 Station 117+24 - CMP - Pearson, A & D - Bituminous Driveway

48 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 7 Station 124+09 - CMP - Nestell, T & P ET AL - Gravel Driveway

48 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 8 Station 126+61 - RCP -Thom, J & C - Gravel Driveway

48 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 9 Station 128+69 - RCP - Weeks, J - Gravel Driveway

50 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 10 Station 129+70 - Steel Culvert - Dankert, J - Gravel Driveway

50 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 11 Station 132+94 - RCP - Revard, M & C - Native Driveway

50 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 12 Station 135+15 - CMP - Revard Revokable Trust - Gravel Driveway

52 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 13 Station 136+59 - CMP - Brown, A & J - Gravel Driveway

54 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 14 Station 138+28 - CMP - Rousseau, T - Bituminous Driveway

64 Lin Ft. 87" x 63" C.M.P.A. (3" x 1" Corr., 10 Ga.)

No. 15 Station 142+61 - CMP - Miller Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

No. 16 Station 144+35 - CMP - Howey, G II & Howey, A - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 17 Station 150+06 - CMP - Alfano, S & P - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 18 Station 151+34 - RCP - Miller Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

No. 19 Station 155+93 - CMP - Bruns Farm Inc. - Gravel Driveway

50 Lin Ft. 54" C.M.P. (3" x 1" Corr., 14 Ga.)

No. 20 Station 171+47 - CMP - Kluck, T & K - Bituminous Driveway

1 Lump Sum Cleanout Existing Crossing

No. 21 Station 172+05 - CMP - Kluck, T & K - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 22 Station 184+18 - RCP - Kluck, T & K - Native Driveway

1 Lump Sum Remove Existing Crossing

No. 23 Station 189+07 - RCP - Kluck, T & K - Gravel Driveway

46 Lin Ft. 42" C.M.P. (2-2/3" x 1/2" Corr., 12 Ga.)

No. 24 Station 193+94 - RCP - Kluck, T & K - Gravel Driveway

46 Lin Ft. 30" C.M.P. (2-2/3" x 1/2" Corr., 12 Ga.)

No. 25 Station 206+25 - CMP - Kluck Properties, LLC - Gravel Driveway

1 Lump Sum Remove & Reinstall Existing Crossing

No. 26 Station 211+20 - CMP - Kluck Properties, LLC - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 27 Station 217+70 - RCP - Van Wormer Road - Bituminous Road

1 Lump Sum Cleanout Existing Crossing

CROSSINGS - SWAN CREEK ROAD BRANCH

No. 28 Station 0+91 - RCP - Gill, H - Bituminous Driveway

1 Lump Sum Cleanout Existing Crossing

No. 29 Station 2+40 - RCP - Mitchell, K - Ruschke, R - Bituminous Driveway

1 Lump Sum Cleanout Existing Crossing

No. 30 Station 2+98 - RCP - Klein, K - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 31 Station 3+69 - RPP - Powell, J & B - Native Driveway

1 Lump Sum Remove and Reinstall Existing Crossing

No. 32 Station 4+58 - RCP - Powell, J & B - Bituminous Driveway

1 Lump Sum Cleanout Existing Crossing

No. 33 Station 5+11 - RCP - Schirmer, S & L - Concrete Driveway

1 Lump Sum Cleanout Existing Crossing

No. 34 Station 6+53 - CPP - Bronz, G & P - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 35 Station 7+46 - RCP - Zuckschwerdt, G & R - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 36 Station 8+18 - CMP - Stutler, W - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 37 Station 9+68 - RCP - Wehner, C - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 38 Station 10+23 - RCP - Hill, M ET AL - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 39 Station 11+23 - RCP - Knapp, D & M - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 40 Station 12+15 - RCP - Hill, M - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

No. 41 Station 13+57 - RCP - Stuller, W - Gravel Driveway

1 Lump Sum Cleanout Existing Crossing

CROSSINGS - BRANCH No. 1

No. 42 Station 1+07 - RCP - Kolhagen, J & K - Gravel Driveway

No. 43 Station 1+23 - RCP - Cass, G ET AL - Bituminous Driveway

62 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

No. 44 Station 3+48 - CMP - Cass, G ET AL - Gravel Driveway

44 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

No. 45 Station 5+41 - RCP - Hill, R JR & P - Gravel Driveway

44 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

No. 46 Station 8+05 - RCP - Banda, L ET AL - Gravel Driveway

40 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

No. 47 Station 8+99 - RCP - Banda, L ET AL - Gravel Driveway

42 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

No. 48 Station 10+57 - CMP - Montgomery, K - Gravel Driveway

50 Lin Ft. 36" C.M.P. (2-3/4" x 1/2" Corr., 12 Ga.)

SOIL EROSION AND SEDIMENT CONTROL

600	Sq. Yds.	Miscellaneous Plain Riprap
100	Lin. Ft.	Grass Spillway
300	Lin. Ft.	Plain Riprap Spillway
200	Lin. Ft.	Plain Riprap Toe of Slope Protection
3	Each	10" and Larger Tile Outlet Repair
15	Each	6" to 8" Tile Outlet Repair
20	Each	4" Tile Outlet Repair
5	Each	35' of 15" CMP Surface Outlet Tube
35	Each	Plain Riprap Splash Pad

MISCELLANEOUS ITEMS

1	Lump Sum	Cleanup and Restoration
1	Lump Sum	Seeding, Fertilizing, and Mulching
1	Lump Sum	Traffic Control

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at the Saginaw County Public Works Commissioner's Office and available to interested parties. Bidding Documents, including plans and specifications, may be examined, beginning April 12, 2024 at the following:

Online at <http://www.saginawcounty.com/PublicWorks/Current-Projects.aspx>

Hard copies of the Contract Documents may be obtained upon payment of a \$200 non-refundable fee, beginning on April 15, 2024. An additional ***non-refundable*** charge of \$10.00 will be required for mailing out Bidding Documents. To order hard copies of the Contract Documents, please contact Ms. Angie McCullen at Spicer Group at (989) 921-5538.

The project will require Davis Bacon Prevailing Wage requirements to be followed by the selected contractor.


A security deposit in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

A **mandatory pre-bid conference** will be held at **3:00 p.m.** on the **17th day of April 2024** at the office of Spicer Group, Inc., 230 S. Washington Avenue, Saginaw, Michigan 48607. It is a requirement that any prospective General Contractor bidding attend this meeting. Representatives of the Owner and Professional will be present to discuss the project. Attendance is required for sealed bids to be accepted. The Professional will transmit to all prospective bidders of record an Addendum as the Professional

considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be legally effective.

The Contract will be awarded to the lowest responsive and responsible bidder giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

Dated: April 8, 2024



Brian J. Wendling
Saginaw County Public Works Commissioner